

Vintage: ten years in service

A newly cut driveway into a relatively stable shale slope made these retaining walls necessary.

Space restrictions ruled out the over-excavation that would be required for composite retaining. Convex indentations and protrusions were incorporated with ease.

A comprehensive drainage system was also specified behind the total wall area, complete with a surface drainage channel above the wall.

Face brick and wrought iron fencing with cobble paving stones rounded off this tricky undertaking, fulfilling all aesthetic expectations.

Today, the installation is almost completely covered in vegetation, softening the overall look even more.

- Contractor: Terrafirma cc
- Engineer: Storey Kiewitz (PTY) Ltd.

For more information:

- Website: www.terraforce.com
- Email: holger@terraforce.com

